ALPINE HVAC SERVICE

Hydronics · Controls
Building Systems

SAMPLE REPORT

Building Performance Audit

Wainfleet Central Fire Station

42143 Hwy 3, Wainfleet · 36 assets · Prepared November 2026

OVERALL SCORE

74 / 100 **B**

Stable; targeted fixes



Equipment condition at a glance

1 RED Act now	**4** YELLOW Monitor or plan repair	**31** GREEN Good condition

SCORECARD · 20 POINTS EACH

Equipment Risk	**13 · Stable**
Controls & BAS	**17 · Strong**
Energy Efficiency	**17 · Strong**
Comfort & IAQ	**15 · Stable**
Vendor & Compliance	**12 · At Risk**

WHAT THE AUDIT FOUND

What's working: 31 of 36 assets are green. Boilers, tube heaters and the 12-piece Mitsubishi system are in good shape on a 2022 plant.

Biggest risk: a leak drained the glycol loop and ran a pump dry before anyone noticed the noise. Repaired, but a repeat could go unseen.

Biggest opportunity: low-cost alarms on loop pressure and controller communication would flag these faults before the building feels them.

If nothing changes: a repeat glycol loss in January could leave the station without in-floor heat: **$4,000–$15,000** in emergency work.

Top findings and budget

24-month plan: **$5,950 – $19,100**

STATUS	FINDING	BUDGET	WHEN
RED	Storage room exhaust fan motor drawing 5.0 A on a 4.0 A rating	$750 – $2,800	0–3 months
YELLOW	Add low-pressure and tank-level alarms to the glycol loop	$900 – $2,800	0–3 months
YELLOW	Annual test due on three backflow preventers	$1,250 – $1,300	0–3 months
YELLOW	Three BAS controllers dropped offline; find the root cause	$800 – $3,500	3–12 months
YELLOW	ERV-1 noise: re-align reheat coil, add duct silencer	$1,200 – $4,800	3–12 months
YELLOW	UV filtration: test water quality, add sleeve cleaning	$400 – $1,900	3–12 months
YELLOW	Zone HZ-04 showing low flow; check the zone valve	$350 – $1,200	3–12 months
GREEN	Complete equipment records (serials on 30 of 36 assets)	$300 – $800	12–24 months

Sample for illustration. Equipment and field observations come from real service records; scores, budgets and timing show the format and are not a completed on-site audit.

ALPINE HVAC SERVICE

Every unit, colour-coded

Wainfleet Central Fire Station · 42143 Hwy 3, Wainfleet

SAMPLE REPORT

HEATING AND HYDRONICS · 12

- Boiler #1 · Lochinvar WHB399N
- Boiler #2 · Raypak XPAK FT 398A
- Radiant tube heaters (2) · Infrasave
- Electric wall heaters (3) · Ouellet
- Heat exchanger HX-1 · Grundfos
- Circulation pumps P-1, P-3 · Grundfos
- **Circulation pump P-2** · Grundfos UPS 32-80F
- **Glycol feed system GFS-1** · Axiom SF100

COOLING · 12

- Condensers CU-1, CU-2 · Mitsubishi
- Fan coils FC-01 to FC-10 · Mitsubishi

VENTILATION · 7

- **Storage room exhaust fan EF-2** · Penn Barry
- **ERV-1** · Systemair TR1800L
- Engine exhaust removal · AirVac 911
- Dehumidifier DH-1 · Engineered Air
- Exhaust fans (3) · Greenheck, Penn Barry

PLUMBING AND WATER · 5

- **UV filtration system** · Viqua PRO50
- Sump pumps SP-01 to SP-03 · Grundfos
- Hot water heater GHWH-1 · AO Smith

Red act now **Yellow** plan **Green** good

WHAT'S BEHIND THE COLOURS

EF-2, red. Motor drawing 5.0 A on a 4.0 A rating, noisy and running hot, pointing to a worn bearing. Replace the motor before it fails.

P-2 and GFS-1, yellow. A loose fitting drained the glycol loop and P-2 ran dry. Leak repaired, loop refilled at 30%. Confirm P-2 is undamaged and add alarms.

UV filtration, yellow. Sensor alarms returned through 2026 and cleared after sleeve cleaning. Test water quality and add sleeve cleaning to maintenance.

ERV-1, yellow. Noise traced toward the reheat coil. Re-align the coil and add a duct silencer.

Beyond the units. Three backflow preventers are due for their annual test, three BAS controllers dropped offline in June, and in-floor zone HZ-04 shows low flow.

Your 12–24 month plan

Low end repairs; high end replaces

NOW · 0–3 MONTHS
$2,900 – $6,900
Fan motor, glycol alarms, backflow tests

NEXT · 3–12 MONTHS
$2,750 – $11,400
Controls, ERV noise, UV, one zone valve

PLAN · 12–24 MONTHS
$300 – $800
Complete the equipment records

AFTER THE AUDIT

Your colours stay current with a live CLEAR report

On a maintenance agreement, this equipment list becomes a live report. Your account manager updates colours and notes as work happens, so you always have a current view for budgets, boards and council.

THE GUARANTEE

Fewer than 3 actionable findings? You don't pay.

Fee fully credited if you sign within 45 days. The report is yours either way.

SCAN, VISIT OR CALL TO BOOK YOUR AUDIT

ALPINEHVAC.CA

289-438-1175